

BID WORKSHEET

The following worksheet is to be used to make your cost proposal. Where quantities are not given, Contractors must calculate their own.

The final pay quantity shall be plan quantity. Generally, the plan quantity was calculated using AutoCAD software, are 3 dimensional, and the dimensions are based on station to station dimensions and widths based on neat lines shown in the Bid Documents. If a bid item of the Contract is found to be in error and so verified by the Engineer, payment will be made in accordance with the corrected plan quantity and adjusted based on the unit price. Only items 2b, 2c, 2g, 2l, and 2m will be based on field measurement. Before and after field measurement will be at the sole cost of the contractor and shall be under the direction of a Professional Licensed Colorado Surveyor.

MONTEZUMA COUNTY LANDFILL CELL 5 CONSTRUCTION

Item #	Description	Quantity	Unit	Unit Price	Total Price
1	Mobilization				
a	Mobilization	1	EA		
				Subtotal 1	
<hr/>					
2	Cell 5	---	---	---	---
a	Clearing and Grubbing	4.75	Acre		
b	Soil Excavation	7,500	CY		
c	Structural Fill	7,500	CY		
d	Liner Subgrade Preparation	210,000	Sq. Feet		
e	Anchor Trench Excavation and Fill	1,500	LF		
f	Cell 4 Liner Tie-in	700	LF		
g	Leachate Collection Layer Gravel	6,200	CY		
h	60-mil HDPE textured Geomembrane	240,000	Sq. Feet		
i	Geosynthetic Clay Liner (GCL)	210,000	Sq. Feet		
j	Geotextile 6-ounce	210,000	Sq. Feet		
k	Geotextile 8-ounce	180,000	Sq. Feet		
l	Protective Cover Soil Material	1,300	CY		
m	Termination Berm	1,000	LF		
				Subtotal 2	
<hr/>					
Total					
<hr/>					